



CLEVELAND CL CY Excavation (unadjusted)			
Station	Area	Volume	Total
0+54.01	104.29	0.00	0.00
1+00	50.37	131.73	131.73
1+43.45	27.41	62.58	194.31
1+77.06	24.63	32.40	226.71
2+57.55	48.67	109.26	335.97
3+00	69.74	93.08	429.05
3+50	84.78	143.08	572.13
4+00	65.77	139.41	711.54
4+50	38.09	96.17	807.71
5+15.35	12.25	60.93	868.63
5+50	33.81	29.55	898.19
6+00	53.81	81.13	979.31
6+60	103.73	175.04	1154.35
6+89.81	137.85	133.37	1287.72
7+34.81	164.90	252.29	1540.01
7+79.81	105.75	225.54	1765.55
8+50	69.55	227.85	1993.40
9+10	60.71	144.73	2138.13
9+50	68.50	95.71	2233.83
10+00	76.24	134.08	2367.91
10+50	89.55	153.52	2521.43
11+00	125.50	197.94	2719.37
11+50	124.34	228.79	2948.16
12+00	139.69	245.96	3194.12
12+50	154.96	274.44	3468.56
13+15	180.94	407.05	3875.61
13+50	157.26	220.16	4095.77
14+00	144.44	279.35	4375.13
14+50	149.64	272.29	4647.42
15+00	139.68	267.89	4915.31
15+50	97.45	219.57	5134.87
16+00	50.02	136.54	5271.42
16+50	37.04	80.61	5352.03
17+00	20.18	52.63	5404.66
17+50	9.60	27.24	5431.90
18+00	2.53	11.02	5442.92
18+75	0.99	4.76	5447.67
19+00	3.48	2.15	5449.82
19+50	40.74	41.17	5490.99
20+00	73.54	105.86	5596.85
20+50	120.23	179.38	5776.23
20+90	130.09	185.43	5961.66
21+50	66.82	218.79	6180.45
22+00	99.49	153.99	6334.44
22+50	143.08	224.60	6559.05
23+00	114.34	238.36	6797.40
23+50	89.13	188.40	6985.80
24+00	97.62	172.92	7158.72
24+50	126.71	207.71	7366.44
24+90	149.49	204.59	7571.03
25+00	144.74	322.55	7893.58
26+00	107.37	230.56	8124.14
26+50	82.94	176.49	8300.63
27+00	30.89	108.02	8408.65
27+36.61	0.28	22.30	8430.95
27+77.09	43.10	34.64	8465.59
28+16.36	63.52	82.05	8547.64
28+50	105.90	109.96	8657.60
29+00	128.71	219.50	8877.11
29+50	106.17	214.51	9091.62
30+06.91	45.70	156.71	9248.33

CLEVELAND CL CY Loose Fill (unadjusted)			
Station	Area	Volume	Total
0+54.01	0.00	0.00	0.00
1+00	34.24	29.17	29.17
1+43.45	32.32	53.56	82.73
1+77.06	40.38	45.26	127.98
2+57.55	21.02	91.51	219.50
3+00	13.69	27.28	246.78
3+50	7.94	20.03	266.81
4+00	4.83	11.82	278.64
4+50	32.65	34.70	313.34
5+15.35	57.12	108.64	421.98
5+50	36.52	60.08	482.06
6+00	21.52	53.74	535.80
6+60	0.38	24.32	560.12
6+89.81	0.00	0.21	560.33
7+34.81	0.00	0.00	560.33
7+79.81	0.00	0.00	560.33
8+50	1.87	2.43	562.76
9+10	7.29	10.18	572.94
9+50	3.29	7.84	580.78
10+00	0.82	3.72	584.49
10+50	0.22	0.89	585.38
11+00	0.03	0.22	585.60
11+50	0.22	0.25	585.85
12+00	0.00	0.20	586.04
12+50	0.00	0.00	586.04
13+15	0.33	0.37	586.41
13+50	0.00	0.21	586.61
14+00	0.31	0.29	586.90
14+50	0.00	0.29	587.19
15+00	0.00	0.00	587.19
15+50	0.00	0.00	587.19
16+00	12.71	11.77	598.96
16+50	22.17	32.29	631.25
17+00	37.75	56.86	688.11
17+50	49.23	82.07	770.18
18+00	60.85	102.96	873.14
18+75	64.29	173.92	1047.06
19+00	65.60	59.30	1106.36
19+50	21.87	79.49	1185.85
20+00	0.12	20.27	1206.12
20+50	0.00	0.10	1206.22
20+90	0.00	0.00	1206.22
21+50	10.70	11.89	1218.12
22+00	6.26	15.71	1233.82
22+50	1.39	7.08	1240.91
23+00	23.28	22.84	1263.75
23+50	27.44	46.97	1310.72
24+00	21.55	45.36	1356.08
24+50	13.29	32.26	1388.34
24+90	8.39	16.06	1404.40
25+00	3.84	14.37	1418.77
26+00	26.55	27.95	1446.72
26+50	63.38	79.35	1526.07
27+00	71.59	118.46	1644.53
27+36.61	108.82	119.28	1763.81
27+77.09	57.41	121.40	1885.21
28+16.36	73.79	90.79	1976.00
28+50	51.52	73.10	2049.10
29+00	12.15	54.23	2103.33
29+50	0.14	10.37	2113.70
30+06.91	0.08	0.23	2113.93

CLEVELAND CL CY Compacted Fill (unadjusted)			
Station	Area	Volume	Total
0+54.01	0.00	0.00	0.00
1+00	0.00	0.00	0.00
1+43.45	0.00	0.00	0.00
1+77.06	0.00	0.00	0.00
2+57.55	0.00	0.00	0.00
3+00	0.00	0.00	0.00
3+50	0.00	0.00	0.00
4+00	0.00	0.00	0.00
4+50	0.00	0.00	0.00
5+15.35	0.00	0.00	0.00
5+50	0.00	0.00	0.00
6+00	0.00	0.00	0.00
6+60	0.00	0.00	0.00
6+89.81	0.00	0.00	0.00
7+34.81	0.00	0.00	0.00
7+79.81	0.00	0.00	0.00
8+50	0.00	0.00	0.00
9+10	0.00	0.00	0.00
9+50	0.00	0.00	0.00
10+00	0.00	0.00	0.00
10+50	0.00	0.00	0.00
11+00	0.00	0.00	0.00
11+50	0.00	0.00	0.00
12+00	0.00	0.00	0.00
12+50	0.00	0.00	0.00
13+15	0.00	0.00	0.00
13+50	0.00	0.00	0.00
14+00	0.00	0.00	0.00
14+50	0.00	0.00	0.00
15+00	0.00	0.00	0.00
15+50	0.00	0.00	0.00
16+00	0.00	0.00	0.00
16+50	0.00	0.00	0.00
17+00	0.00	0.00	0.00
17+50	0.00	0.00	0.00
18+00	0.00	0.00	0.00
18+75	0.00	0.00	0.00
19+00	0.00	0.00	0.00
19+50	0.00	0.00	0.00
20+00	0.00	0.00	0.00
20+50	0.00	0.00	0.00
20+90	0.00	0.00	0.00
21+50	0.00	0.00	0.00
22+00	0.00	0.00	0.00
22+50	0.00	0.00	0.00
23+00	0.00	0.00	0.00
23+50	0.00	0.00	0.00
24+00	0.00	0.00	0.00
24+50	0.00	0.00	0.00
24+90	0.00	0.00	0.00
25+00	0.00	0.00	0.00
26+00	0.00	0.00	0.00
26+50	0.29	0.25	0.25
27+00	44.70	40.27	40.51
27+36.61	92.22	91.49	132.00
27+77.09	51.28	106.00	238.00
28+16.36	11.73	44.20	282.20
28+50	0.01	6.82	289.02
29+00	0.00	0.01	289.03
29+50	0.00	0.00	289.03
30+06.91	0.00	0.00	289.03



**BAUGHMAN  
COMPANY**  
315 Ellis St.  
Wichita, KS 67211  
316-262-7271  
BaughmanCo.com

CORNEJO INDUSTRIAL  
DISTRICT

**CROSS  
SECTIONS**

STREET IMPROVEMENTS  
Street Paving Improvements

PROJECT NUMBER:  
472-2021-085726

DESIGN: PSB DRAWN: HJW  
DATE: Oct. 26, 2021

SHEET OF  
**56 62**