



POLE SCHEDULE

POLE NO	POLE MATERIAL	POLE HEIGHT	MOUNTING HEIGHT	ARM LENGTH	REMARKS
F	FIBERGLASS	40'-0"	40'-0"	6'-0"	SEE NOTE 1 & 3
W	WOOD	35'-0"	31'-0"	6'-0"	SEE NOTE 1, 2 & 3

LIGHTING FIXTURE NOTES

- POLE, FIXTURE ARM AND LIGHT FIXTURE TO BE INSTALLED BY EVERYG.
- INSTALL POLE SUCH THAT THE FIXTURE HEAD IS ABOVE THE EDGE OF THE ROADWAY.
- POLE AND MOUNTING HEIGHTS ARE PROVIDED AS A BASIS OF DESIGN. ALL STREET LIGHTING EQUIPMENT SHALL BE INSTALLED PER EVERYG'S INSTALLATION REQUIREMENTS.

- STREET LIGHTING CONTRACTOR VERSUS UTILITY RESPONSIBILITIES:**
- THE CONTRACTOR SHALL:
 - SUPPLY AND INSTALL ALL CONDUIT.
 - SUPPLY AND INSTALL ALL HANDHOLES.
 - THE UTILITY SHALL:
 - SUPPLY AND INSTALL ALL CONDUCTORS.
 - SUPPLY AND INSTALL ALL OVER-CURRENT & OVER-LOAD PROTECTION.
 - SUPPLY AND INSTALL ALL POLES, POLE ARMS, AND LIGHT FIXTURES.
 - TERMINATE THE SECONDARY CONDUCTORS AT THE UTILITY TRANSFORMER.
 - NO JUNCTION BOXES SHALL BE ALLOWED ON THE BRIDGE FOR THE STREET LIGHTING CONDUIT ROUTING.
 - EVERY CONTACT:
 - SHANE PRICE, (316) 261-6315, Shane.Price@evergy.com

- ENGINEERS NOTES:**
- BASIS OF DESIGN LUMINAIRE IS: AEL, CATALOG #ATBM-P20-R3-4K.
 - ROADWAY FUNCTIONAL CLASSIFICATION: MINOR ARTERIAL, INTERMEDIATE PEDESTRIAN ACTIVITY
 - AASHTO GL-7-2018 CRITERIA: 0.8 fc AVERAGE. 4:1 AVE/MIN.

SEE SHEET 77 FOR CONTINUATION

PREPARED BY
 EVERGY
77 NORTH WACO
SUITE 200
WICHITA, KANSAS 67203
PHONE: 316-362-9333

CONSULTANTS:

AMIDON AVE BRIDGE REPLACEMENT & ROAD IMPROVEMENTS
WICHITA, KANSAS
 CITY OF WICHITA

REVISIONS:	MARK	DATE	DESCRIPTION

PROJ NO: R210326.00
SCALE:
DATE: 7/13/2022
DESIGNED BY: AJM
DRAWN BY: AJM
CHECKED BY: JTS

SHEET TITLE:
STREET LIGHTING PLAN

SHEET NO.
77
SHEET 77 OF 128

A:\2022\PROJECTS\20220713\20220713_01 - Wichita Avon Bridge over Arkansas River - Study Design\Drawings\20220713_01_ELEC_FULL_SIZE.dwg, 11/13/2022, 10:54:14 AM