




NOTES:

1. This Plan Is Not To Be Used As A Comprehensive Grading Plan. All Spot Elevations Are Proposed & Subject To Change.

2. Each Lot Area Disturbed By Construction Shall Be the Responsibility of Each Individual Homeowner. Owner Responsible To Follow All SWPP Plans & Guidelines For The Area.

3. Erosion Control Matting and/or Other Approved Bank Stabilization w/Seeding & Fertilizer Shall Be Installed at Engineered Channels or Sediment Basins Where the Designed Sideslopes Will be Greater Than 6:1. All Other Disturbed Areas Shall be Seeded, Fertilized, & Mulched As Follows:

Seeding: See Mass Grading and Pond Plan Sheets

4. Install 8' Wide Culex/Excelsior Blanket, or Approved Equal, on Prepared Surface Back of Curb or Edge of Asphalt. Edge of Blanket Will Be At Back of Curb or Edge of Asphalt. Install Per Manufacturers Recommendation, Including Staples.

5. The Silt Fence Install Around the Pond May be Substituted with a 40' Wide Strip of Mat-Blend 50/50 Plus Wood Fiber Mulch. The Seeding Rate Shall Be the Same As Note 3. Contact Mat, Inc. For More Information on Mat-Blend Plus at 1-888-477-3028. Mat-Blend Plus May be Substituted For Another Comparable Hydro-Mulch Product.

EROSION CONTROL PLAN LEGEND

(Installation Details Found in the SWP2 Plan)

- LIGHT STONE RIP-RAP
- DROP INLET PROTECTION
- CURB INLET PROTECTION
- SILT FENCING

NO SCALE

Scale: 1" = 30' Horizontal

EROSION CONTROL MEASURE	UNITS	QUANTITY
SILT FENCE	L.F.	2,280
RIPRAP	S.Y.	**
DROP INLET BARRIER	EA.	7
CURB INLET BARRIER	EA.	2
Construction Entrance	EA.	2

QUANTITIES ARE FOR INFORMATION ONLY
CONTRACTOR SHALL VERIFY QUANTITIES PER
SPECIFIC ENGINEERING PLAN SHEET.

** See Plan Sheets for Quantities

		My House Addition	
		Erosion Control Plan	
Baughman Company, P.A., 315 Elm St., Waltham, MA 02451 ENGINEERING SURVEYING PLANNING LANDSCAPE ARCHITECTURE		DESIGN	DRAWN
PROJECT NUMBER	47284049	Staff	Staff
REVISIONS		APPROVED	DATE
		SCALE	08/04
		Noted	
		SHEET	
		7 OF 16	