FHWA REG NO.	STATE	PROJECT NO.	YEAR	SHEET NO.	SHEETS
7	KANSAS	87N 0064-01	1997	11	130

P.I. STA. 97+21.91
E 1/4 Sec. 31, T27S, R1E
1. Found Pipe in Thimble @ Seneca & May
2. NE Face HLP 45.9' S.W.
3. NW Cor. Brick Column 51.6' N.W.
4. NW Face HLP 56.0' N.W.
5. SW Cor. House Foundation 73.5' E.

Sta. 48+98.46 May, Saw Cut & Match Exist. Pav't. Drill and Grout Deformed Tie Bar #5 x 24" @ 24" O.C. Cost is Subsidiary to Concrete Pavement (9" Uniform)(AE)(NRDJ)

Sta. 48+98.46 May, Construct Concrete Collar and Connect 60" RCP to Existing 48" RCP Install 60" x 4' (RCP) Storm Swr. (E) See Sht. No. 50, 53

(90) Sta. 49+04.14 May, Construct Reinf. Conc. Manhole, 5.83' Lt. L=9'6", W=6'2" Manhole Top=1288.37 Install 6' x 4' x 100' (RCB) Storm Swr. (E) See Sht. No. 39, 42D, 43, 50

Sta. 49+04.14 May, Construct Curb Inlet (Type II), 14.88' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1288.70 Install 15" x 16' Storm Swr. (RCP)(N) See Sht. No. 38, 50

(91) Sta. 49+04.14 May, Construct Curb Inlet (Type II), 14.88' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1288.74 Install 15" x 5' Storm Swr. (RCP)(S) See Sht. No. 38, 50

(89) Sta. 49+10.51 May, Construct Curb Inlet (Type II), 14.88' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1288.56 Install 15" x 2' Storm Swr. (RCP)(W) See Sht. No. 38, 50

Const. Limits (87)

Sta. 97+68.67 Seneca, Construct Curb Inlet (Type II), 29.68' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1287.26 Install 15" x 37' Storm Swr. (RCP)(E) See Sht. No. 38, 50

(84) Saw Cut & Match Exist. Pav't. 49' Lt.

Sta. 98+27.64 Seneca, Relocate Exist. Water Meter. See Sht. No. 53

Sta. 98+98.54 Seneca, Relocate Exist. Water Meter. See Sht. No. 53

Sta. 99+03.16 Seneca, Relocate Exist. Water Meter. See Sht. No. 53

Sta. 99+05.30 Seneca, Relocate Exist. Water Meter. See Sht. No. 53

Saw Cut & Match Exist. Pav't. 49' Lt.

Saw Cut & Match Exist. Pav't. 49' Lt.



Sta. 97+21.91 Install Monument Box See Sht. No. 53

Saw Cut & Match Exist. Pav't. 49' Rt.

Sta. 97+59.60 Seneca, Relocate Exist. Water Meter. See Sht. No. 53

(92) Sta. 97+27.67 Seneca, Construct Reinf. Conc. Manhole, 11.50' Rt. L=9'6", W=13'8" Manhole Top=1287.03 Install 10' x 4' x 260' (RCB) Storm Swr. (S) See Sht. No. 39, 42B, 43, 50

(85) Sta. 97+67.85 Seneca, Construct Curb Inlet (Type II), 29.68' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1287.26 Install 15" x 14' Storm Swr. (RCP)(W) See Sht. No. 38, 50

Saw Cut & Match Exist. Pav't. 49' Rt.

Sta. 98+39.68 Seneca, Relocate Exist. Water Meter. See Sht. No. 53

(86) Sta. 97+64.14 Seneca, Construct Manhole (Type B), 11.50' Rt. Stack on Top of 10' x 3' RCB Manhole Top=1287.15 See Sht. No. 40, 50, 53

Saw Cut & Match Exist. Pav't. 49' Rt.

Sta. 100+09.82 Seneca, Relocate Exist. Water Meter. See Sht. No. 53

Sta. 100+43.45 Seneca, Relocate Exist. Water Meter. See Sht. No. 53

Saw Cut & Match Exist. Pav't. 49' Rt.

Saw Cut & Match Exist. Pav't. 49' Rt.

Sta. 100+73.69 Seneca, Relocate Exist. Water Meter. See Sht. No. 53

Saw Cut & Match Exist. Pav't. 49' Rt.

Sta. 101+47.65 Seneca, Relocate Exist. Water Meter. See Sht. No. 53

LEGEND
PAVEMENT, DRIVEWAY AND/OR SIDEWALK REMOVAL.

BM #11 City disc in sidewalk NW cor. May & Seneca. Sta. 97+55.28 46.99' Lt. Elev.=1288.42

UTILITY OWNERS

W – City of Wichita Water & Sewer Department (316)268-4908
T – Southwestern Bell Telephone Co. 1-571-2115
E – Kansas Gas and Electric (316)832-3169 or 832-3180
CATV – Multimedia Cablevision (316)262-4270
SS – City of Wichita Water & Sewer Department (316)268-4908
SWS – City of Wichita Water & Sewer Department (316)268-4908

KANSAS DEPARTMENT OF TRANSPORTATION

SOUTH SENECA STREET
97+00 TO 102+00

PROJECT NO. 87N 0064-01 SEDGWICK CO.

MID-KANSAS ENGINEERING CONSULTANTS, INC.
WICHITA, KANSAS

DESIGNED BY: GJA	CHECKED BY: GJA	
DRAWN BY: WNJ	DATE: 8/95	SHEET 11 OF 130

94005E13

H:\CIVIL\SENECA\94005\PAVE\94005E13 Fri May 30 11:08:01 1997