



BLAKE CY Excavation (unadjusted)				BLAKE CY Compacted Fill (unadjusted)				BLAKE CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total	Station	Area	Volume	Total
2+96.61	15.46	0.00	0.00	2+96.61	0.98	0.00	0.00	2+96.61	11.71	0.00	0.00
3+50	15.41	30.52	30.52	3+50	1.02	1.70	1.70	3+50	10.11	21.88	21.88
4+00	15.49	28.61	59.12	4+00	0.99	1.59	3.29	4+00	10.14	18.87	40.75
4+50	15.46	28.66	87.78	4+50	0.98	1.62	4.91	4+50	10.16	18.90	59.66
4+83.26	15.45	19.04	106.82	4+83.26	0.97	1.20	6.11	4+83.26	11.12	13.10	72.76
5+20.23	30.74	31.63	138.45	5+20.23	0.00	0.66	6.77	5+20.23	0.00	7.61	80.37
5+57.27	15.46	31.69	170.14	5+57.27	0.98	0.67	7.45	5+57.27	11.09	7.61	87.98
6+00	15.46	24.47	194.61	6+00	0.98	1.55	9.00	6+00	10.16	16.81	104.80
6+50	15.46	28.63	223.25	6+50	0.99	1.79	10.79	6+50	10.16	18.82	123.62
6+78.50	15.56	16.37	239.62	6+78.50	0.97	1.00	11.80	6+78.50	10.09	10.70	134.32



**BAUGHMAN
COMPANY**
315 Ellis St.
Wichita, KS 67211
316-262-7271
BaughmanCo.com

TURKEY CREEK 4TH
ADDITION - PHASE III
**EARTHWORK
CROSS
SECTIONS**

Street Paving Improvements
PROJECT NUMBER:
472-2020-085620
DESIGN: DMV DRAWN: JAK
DATE: Sept. 18, 2023
SHEET **21** OF **28**

File: E:\Projects\Turkey Creek 4th Addition\Engineering\Phase 3\STR_22-06-E217\STR_22-06-E217.dwg