


GREENLEAF ST

GREENLEAF CT CY Excavation (unadjusted)			
Station	Area	Volume	Total
-0+35	8.75	0.00	0.00
-0+15	25.86	12.82	12.82
0+00	30.39	15.62	28.44
0+23.43	21.82	22.65	51.09
0+50	15.46	18.34	69.43
1+00	15.46	28.63	98.07
1+50	15.46	28.63	126.70
2+00	15.46	28.63	155.34
2+50	15.65	28.81	184.15
3+00	15.46	28.81	212.96
3+50	15.46	28.63	241.60
3+84.96	15.46	20.02	261.62
4+21.98	21.80	25.54	287.16
4+58.96	16.32	26.10	313.25
5+00	15.46	24.15	337.41
5+50	15.46	28.63	366.04
6+00	15.46	28.63	394.68
6+50	15.46	28.63	423.31
6+79.12	15.39	16.64	439.95

GREENLEAF CT CY Loose Fill (unadjusted)			
Station	Area	Volume	Total
-0+35	22.50	0.00	0.00
-0+15	11.46	12.57	12.57
0+00	10.62	6.13	18.71
0+23.43	12.94	10.22	28.93
0+50	10.67	11.62	40.55
1+00	10.67	19.76	60.31
1+50	10.67	19.76	80.07
2+00	10.67	19.76	99.83
2+50	10.67	19.76	119.59
3+00	10.67	19.76	139.35
3+50	10.67	19.76	159.10
3+84.96	10.67	13.81	172.92
4+21.98	5.36	10.99	183.91
4+58.96	11.11	11.28	195.19
5+00	11.14	16.91	212.09
5+50	11.14	20.63	232.72
6+00	11.14	20.63	253.35
6+50	11.14	20.63	273.98
6+79.12	11.12	12.01	285.99



**BAUGHMAN
COMPANY**
315 Ellis St.
Wichita, KS 67211
316-262-7271
BaughmanCo.com

TOWNE PARC 10TH
ADDITION PHASE 1

**EARTHWORK
CROSS
SECTIONS**

Street Paving Improvements

PROJECT NUMBER:

DESIGN: NBW DRAWN: JLD
DATE: 29 August 2023

SHEET OF
30 43

File: E:\Projects\Towne Parc 10th Addition_22-01-P743\Engineering\PHASE 1\STR_22-11-E355\STR.dwg