




Scale: 1" = 60'

- NOTES:**
1. This Plan Is Not To Be Used As A Comprehensive Grading Plan. All Spot Elevations Are Proposed & Subject To Change.
 2. Each Lot Area Disturbed By Construction Shall Be the Responsibility of Each Individual Homeowner. Owner Responsible To Follow All SWPP Plans & Guidelines For The Area.
 3. Erosion Control Matting and/or Other Approved Bank Stabilization w/Seeding & Fertilizer Shall Be Installed at Engineered Channels or Sedimentation Basins Where the Designed Sideslopes Will be Greater Than 8:1. All Other Disturbed Areas Shall be Seeded, Fertilized, & Mulched per General Note 11.
 4. Install 6' Wide Curlex/Excelsior Blanket, or Approved Equal, on Prepared Surface Back of Curb. Edge of Blanket Will Be At Back of Curb. Install Per Manufacturers Recommendation, Including Staples.
 5. The Earth Dikes Constructed Around the Ponds May be Substituted with Silt Fence with Approval of Developer.
 6. All Seeding Shall Be Drilled During Spring or Fall Planting Seasons. Fall Seeding Shall Be September 1 thru Mid October. Spring Seeding Shall be From March 15 thru Mid May.
 7. Install Curlex/Excelsior Blanket, or Approved Equal, on Prepared Surface where Soil Has Been Disturbed Due To Construction of Drive Entrances Joining into the Exist. Arterial Street.

**EROSION CONTROL PLAN
LEGEND**

(Installation Details Found in the SWPP Plan)

- LIGHT STONE RIP-RAP
- DROP INLET PROTECTION
- CURB INLET PROTECTION
- SILT FENCING
- EARTH DIKES

NO SCALE

EROSION CONTROL MEASURE	UNITS	QUANTITY
SILT FENCE	L.F.	65
RIPRAP	S.Y.	79
(See Plan Sheets)		
DROP INLET BARRIER	EA.	5
(See Plan Sheets)		
CURB INLET BARRIER	EA.	7
(See Plan Sheets)		
STRAW BALE DITCH CHECK	EA.	maintain
EARTHEN DIKES	L.F.	maintain
CURLEX	S.Y.	2,453
POND E.C. BLANKET	S.Y.	maintain
Construction Entrance	EA.	1

QUANTITIES ARE FOR INFORMATION ONLY!
CONTRACTOR SHALL VERIFY QUANTITIES PER
SPECIFIC ENGINEERING PLAN SHEET.



Harvest Ridge Addition - Phase II
**Erosion Control
Plan**
Street & SWS Improvements

Baughman Company, P.A. 315 Ellis St., Raleigh, NC 27601 F 316-332-3111 F 316-332-0149
ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE

PROJECT NUMBER
472-83805

DESIGN
JAK
APPROVED
DATE
4/12/06

REVISIONS

SCALE
1" = 60'
SHEET

19 OF 34

F:\Eng\harvest Ridge\Phase II\ECPLAN (StrEC)

06-01-E485