LEGEND

Removal

Tree Removal

(XXX) Note: For the project control & Coordinate Data, See Sheets 3-5

VC = 75'
K = 170

-0.24% | -0.24% | +0.20% | +0.20%

Sta. 89+50.00
P.V.I. Elev. = 1,292.66
Match Existing

Sta. 90+31.50
P.V.C. Elev. = 1,292.46

Sta. 90+69.00
P.V.I. Elev. = 1,292.37

Sta. 91+06.50
P.V.T. Elev. = 1,292.45

SCALE: 1"=20'
20' 0 20' 40'

Sta. 90+62.06, 28.28' Lt.
Replace Ring and Cover
Adjust Exist. Sanitary Manhole
Exist. Elev. = 1292.83
Prop. Elev. = 1291.82
Difference = -1.01'

Sta. 90+65.90, 38.66' Lt.
Replace Ring and Cover
Adjust Exist. Sanitary Manhole
Exist. Elev. = 1293.39
Prop. Elev. = 1292.74
Difference = -0.65'

Sta. 89+98.18, 40.18' Lt.
End 10.0' Radius

Sta. 89+90.36, 43.96' Lt.
End 16.0' Radius
Begin 10.0' Radius

Sta. 89+77.85, 50.00' Lt.
Begin 16.0' Radius

Sta. 89+65.00, 47.00' Lt.
Const. 6.0' Concrete Sidewalk (4")

Sta. 89+50.00, 47.50' Lt.
Const. Concrete Sidewalk (4")
Saw Cut Neat Line
Match Exist.

Sta. 89+50.00, 24.93' Lt.
Begin Taper (BOC)
Const. Type I Curb & Gutter (6")
Top of Curb Elev. = 1293.11
Match Exist.

(402)

Sta. 89+50.00
Begin Full Depth
Concrete Pavement (9")(NRDJ)
Saw Cut Neat Line
Match Exist.
See Sheet 126-127

Sta. 89+21.20, 47.36' Lt.
End 16.0' Radius

Sta. 90+17.48, 43.96' Lt.
End 10.0' Radius
Begin 16.0' Radius

Sta. 90+09.65, 40.18' Lt.
Begin 10.0' Radius

Wescon Controls LLC
2533 S. West St.
Wichita, KS 67213

Wescon Controls LLC
2533 S. West St.
Wichita, KS 67213

M.H.
Fiberglass Systems LP
2501 S. West St.
Wichita, KS 67213

Sta. 90+45.66, Lt.
℄ 8" Concrete Drive
31.3' Width

Sta. 90+91.50, Lt.
℄ 8" Concrete Drive
17.0' Width

Temp. Esmt.

Temp. Esmt.

Temp. Esmt.

Exist. R/W

Exist. R/W

Exist. R/W

Prop. R/W

Exist. R/W

BM #211

WEST STREET

℄ Proposed Improvements = ℄

Profile Grade Line

Profile Grade Line

110' R/W

60' ℄ to R/W

50' ℄ to R/W

MATCHLINE STA. 91+25.00

Exist. Fence

Const. Limits

Exist. R/W

Prop. R/W

Exist. Metal Fence
(to be Removed by others)

Sta. 89+50.00
Begin Proj. No. E8049-40103918 =
KDOT Proj. No. 87 N-0720-01

(401)

Sta. 89+50.00, 24.68' Rt.
Begin Taper (BOC)
Const. Type I Curb & Gutter (6")
Top of Curb Elev. = 1292.64
Match Exist.

Sta. 89+50.67, 25.17' Rt.
Remove and Reset Mailbox

Arrow Holding Company LLC
2510 S. West St.
Wichita, KS 67213

Sta. 89+50.00, 47.63' Rt.
Const. Concrete Sidewalk (4")
Saw Cut Neat Line
Match Exist.

Sta. 89+50.00, 49.66' Rt.
Begin 10.0' Radius

Sta. 89+57.72, 52.99' Rt.
End 10.0' Radius
Begin 21.0' Radius

Sta. 89+71.56, 59.92' Rt.
End 21.0' Radius

Sta. 89+71.57, 57.00' Rt.
Const. 6.0' Concrete Sidewalk (4")

Sta. 89+87.47, Rt.
℄ 8" Concrete Drive
30.0' Width

Sta. 90+61.99, 27.59' Rt.
Replace Ring and Cover
Adjust Exist. Sanitary Manhole
Exist. Elev. = 1292.93
Prop. Elev. = 1291.85
Difference = -1.08'

SE Cor. Sec. 1 T28S R1W
Sta. (N 1,670,348.0506 E 1,634,134.6643)
★ ½" Iron bar with cap "S-E CLS 59"
1. MAG nail with washer found in the Northeast face of a power pole. 31.11' SW
2. MAG nail with washer found in the Northeast face of a power pole. 50.21' SW
3. 3 nails with shiner found in the East face of a light pole. 118.93' SW

BM #211
"□" cut set on SE corner of an electric transformer pad located at SE corner of building of 2533 S West Street.
N 1,671,512.3687
E 1,634,071.9975
Sta. 85+58.97, 51.70' Lt. Elev. = 1293.71

IF THIS DRAWING IS LESS THAN 22" X 36" IT IS A REDUCED SIZE DRAWING

TRANSYSTEMS
245 N. WACO
SUITE 222
WICHITA, KANSAS 67202
MAIN: 316-303-3000
FAX: 316-462-5629

CONSULTANTS:

REVISIONS:

MARK	DATE	DESCRIPTION

WEST STREET IMPROVEMENTS
FROM PAWNEE TO HARRY

WICHITA, KANSAS

CITY OF WICHITA

PROJ NO: 87 N-0720-01
SCALE: 1"=20'
DATE: 9/25/2023
DESIGNED BY: CKC
DRAWN BY: CKC
CHECKED BY: MDB

SHEET TITLE:

WEST STREET
PLAN & PROFILE
STA. 89+50.00 TO
STA. 91+25.00

SHEET NO.
13
SHEET 13 OF 517

lcrahe
9/25/2023 - 6:18:03 PM - c:\transystems\ow_local\transyscorp-pw1\ea_local\ds8984549\C-RDW-M01-101.DGN