

*City of Wichita Benchmark located
41.60' North and 69.00' East of the
Centerlines of Hoover and MacArthur
(39th St. South)*

*City of Wichita Benchmark located
at East end of Bridge over the Big
Ditch on MacArthur in the West bound
lane.*

Sta 0+00, Line 1
Begin Construction of 42" RCP
w/ RC Headwall and 20.0 S.Y.
Heavy Stone Rip-Rap.

BLUE LAKE
ADDITION

Note: Contractor shall Remove Trees only as Necessary to Construct Sanitary Sewer Line. Cost of Tree Removal shall be Included in Bid Item "Site Clearing and Restoration."

Sta 0+00 to Sta 0+42.4
Install 42.4 L.F. Flowable Fill
Fill Per City Specs.

Sta 0+42.4, End Line
Construct std. type
1A inlet. (10'x3')
Top Elev. = 101.90

Sta 2+31.4, Line 1
Construct Std. Manhole
(6' Dia.)
1 - 24" Stub (S)
Top Elev. = 103.20

Sta 1+84.8 to Sta 2+23.9
Install 39.1 L.F. Flowable
Fill Per City Specs.

BLUE LAKE
ADDITION

CAUTION!
*Ex. 8" Sewer
Line Crossing*

Sta 3+47.4, Line 1
= Sta 0+00, Line 1A
Construct Std. Manhole
(6' Dia.)
Top Elev. = 102.20

Sta 3+77.7, Line 1
= Sta 0+00, Line 1C
Construct std. type
1A inlet. (10'x5')
Top Elev. = 101.90
Match Point

Scale: 1" = 20' Horizontal
1" = 5' Vertical
● = Iron

