1. Removal of curb shall not be paid separately but shall be INCLUDED in the bid item "Pavement Removed"
2. Curb & Gutter (Type 1) (150mm), Curb & Gutter (Type 1) (150mm) (Low Edge), Curb & Gutter (Type 3) (150mm), and Curb & Gutter (Type 3) (200mm) shall be paid for as "Curb and Gutter (Combined) (AE)."
3. Removal of Inlets, Manholes, Storm Sewer Pipe, Light Poles, and etc. shall be SUBSIDIARY to "Removal of Existing Structures."
4. Abandoning Storm Sewer Pipe using Pipe Plugs shall be SUBSIDIARY to "Removal of Existing Structures."
5. All Wheelchair Ramps regardless of width shall be paid for as "Sidewalk Construction (100mm) (AE)."
6. Removal & Reinstallation of Paving Bricks shall be SUBSIDIARY to "Paving Brick."
7. Common Excavation within the Project limits shall be SUBSIDIARY to the Project.
8. The bid item "Erosion Control" shall include, but not be limited to, Silt Fences, Inlet Barriers, Erosion Mats, and/or any other 'Best Management Practices' (BMPs) necessary to inhibit downstream sediment laden runoff.

RECAPITULATION OF ROAD & PROJECT QUANTITIES

ITEM	QUANTITY TOTAL	UNIT
PAVING BID ITEMS		
ASPHALT PAVEMENT 180mm (130mm BIT. BASE)	2684	sq. m
CONCRETE PAVEMENT (200mm UNIF) (AE)	1449	sq. m
CRUSHED STONE SUBGRADE (180mm)	1565	sq. m
CRUSHED STONE SUBGRADE (200mm)	3303	sq. m
GEOGRID REINFORCEMENT (FOR BASE)	4868	sq. m
CURB AND GUTTER (COMBINED) (AE)	696	m
CONCRETE RAMP NOSE SECTION	6	EACH
SIDEWALK CONSTRUCTION (100mm) (AE)	290	sq. m
80mm PAVING BRICK (CROSSWALKS)	320	sq. m
60mm PAVING BRICK (MEDIANS)	310	sq. m
PAVEMENT REMOVED	4684	sq. m
SITE CLEARING & RESTORATION	LUMP SUM	LUMP SUM
REMOVAL OF EXISTING STRUCTURES	LUMP SUM	LUMP SUM
DRAINAGE BID ITEMS		
STORM SEWER (375mm)	76	m
INLET (TYPE 1) (SINGLE)	2	EACH
INLET (TYPE 1) (DOUBLE)	2	EACH
MANHOLE (SPECIAL SHALLOW, TYPE B)	1	EACH
ADJUSTMENT OF MANHOLES (INCL NEW RING & COVER)	4	EACH
TRAFFIC & PROJECT BID ITEMS		
TRAFFIC SIGNAL INSTALLATION (PERMANENT)	LUMP SUM	LUMP SUM
TRAFFIC SIGNAL INTERCONNECT	LUMP SUM	LUMP SUM
PAVEMENT MARKING	LUMP SUM	LUMP SUM
PROJECT SIGNAGE	LUMP SUM	LUMP SUM
CONSTRUCTION TRAFFIC CONTROL	LUMP SUM	LUMP SUM
PROJECT EROSION CONTROL	LUMP SUM	LUMP SUM
100mm PVC IRRIGATION SLEEVE CONDUIT	83	m
50mm PVC STREET LIGHT CONDUIT (JOINT USE POLES)	190	m
ADD ALTERNATE BID ITEMS		
LIGHT COLUMN INSTALLATION (CENTRAL & MCLEAN)	LUMP SUM	LUMP SUM
SEE SH. NO. 23 SUMMARY OF LIGHT COLUMN QUANTITIES		
SEE SH. NO. 26 SUMMARY OF TRAFFIC SIGNAL QUANTITIES		
SEE SH. NO. 32 SUMMARY OF SIGNING AND PAVEMENT MARKING QUANTITIES		

METRIC

DESIGN	DATE	CITY PROJECT NUMBER	BAUGHMAN PROJECT NUMBER
STAFF	JULY99	472-78-245-82910	98-01-E965
DRAWN	SCALE	APPROVED	DIRECTORY
STAFF	NONE	JFB	F:\MCLNINT\QTY
			SPREADSHEET
			TABLSUM1.DWG

CAPITAL IMPROVEMENT PROJECT
SUMMARY OF QUANTITIES
CENTRAL & MCLEAN INTERSECTION IMPROVEMENTS

BAUGHMAN COMPANY P. A.
ENGINEERING, SURVEYING, & PLANNING
316-262-7271 • 315 ELLIS • WICHITA, KANSAS 67211