

AC PAVEMENT (8") (6" BIT. BASE)

SHEET NO.	CL STATION	CL STATION	SQ. YDS.
5	11+08.03	15+50.00	1778
6	15+50.00	20+77.03	2257
7	20+77.03	28+50.00	1972
8	28+50.00	32+00.00	2093
9	32+00.00	37+75.00	2172
10	37+75.00	43+65.90	2465
11	43+65.90	49+00.00	2018
12	49+00.00	54+50.00	2284
13	54+50.00	60+00.00	2883
14	60+00.00	62+39.54	1638
TOTAL			21546

REINFORCED CRUSHED ROCK BASE (8")

SHEET NO.	CL STATION	CL STATION	SQ. YDS.
5	11+08.03	15+50.00	2120
6	15+50.00	20+77.03	2687
7	20+77.03	28+50.00	2328
8	28+50.00	32+00.00	2511
9	32+00.00	37+75.00	2819
10	37+75.00	43+65.90	2925
11	43+65.90	49+00.00	2433
12	49+00.00	54+50.00	2713
13	54+50.00	60+00.00	3311
14	60+00.00	62+39.54	1824
TOTAL			25451

6" CRUSHED ROCK BASE (UNDER DRIVES)

SHEET NO.	CL STATION	CL STATION	SQ. YDS.
5	11+08.03	15+50.00	38
6	15+50.00	20+77.03	417
7	20+77.03	28+50.00	110
8	28+50.00	32+00.00	299
9	32+00.00	37+75.00	53
10	37+75.00	43+65.90	87
12	49+00.00	54+50.00	
TOTAL			1002

7" CRUSHED ROCK BASE (UNDER RCVG)

SHEET NO.	CL STATION	CL STATION	SQ. YDS.
7	20+77.03	26+50.00	210
8	26+50.00	32+00.00	34
10	37+75.00	43+65.90	239
TOTAL			483

RCVG PAVEMENT (8" W/7" ROCK SUBGRADE)

SHEET NO.	CL STATION	CL STATION	SQ. YDS.
7	20+77.03	26+50.00	205
8	26+50.00	32+00.00	40
10	37+75.00	43+65.90	278
TOTAL			523

AC BASE COURSE (BC-1) 3"

SHEET NO.	CL STATION	CL STATION	SQ. YDS.
5	11+08.03	15+50.00	338
6	15+50.00	20+77.03	316
7	20+77.03	28+50.00	341
8	28+50.00	32+00.00	373
9	32+00.00	37+75.00	382
10	37+75.00	43+65.90	438
11	43+65.90	49+00.00	424
12	49+00.00	54+50.00	399
13	54+50.00	60+00.00	419
14	60+00.00	62+39.54	175
TOTAL			3561

COMB C & G (6 5/8" & 1 1/2")

SHEET NO.	CL STATION	CL STATION	LF
5	11+08.03	15+50.00	884
6	15+50.00	20+77.03	812
7	20+77.03	28+50.00	878
8	28+50.00	32+00.00	958
9	32+00.00	37+75.00	932
10	37+75.00	43+65.90	1121
11	43+65.90	49+00.00	1040
12	49+00.00	54+50.00	1028
13	54+50.00	60+00.00	1077
14	60+00.00	62+39.54	450
TOTAL			9158

CONCRETE FLUME

SHEET NO.	CL STATION	CL STATION	LF
6	15+50.00	20+77.03	14
TOTAL			14

EXCAVATION (CUT)

SHEET NO.	CL STATION	CL STATION	CU. YDS.
5	11+08.03	15+50.00	1243
6	15+50.00	20+77.03	753
7	20+77.03	28+50.00	1072
8	28+50.00	32+00.00	1824
9	32+00.00	37+75.00	2800
10	37+75.00	43+65.90	1905
11	43+65.90	49+00.00	1789
12	49+00.00	54+50.00	2537
13	54+50.00	60+00.00	3805
14	60+00.00	62+39.54	1357
TOTAL			19065

LOOSE FILL

SHEET NO.	CL STATION	CL STATION	CU. YDS.
5	11+08.03	15+50.00	477
6	15+50.00	20+77.03	791
7	20+77.03	28+50.00	484
8	28+50.00	32+00.00	321
9	32+00.00	37+75.00	77
10	37+75.00	43+65.90	708
11	43+65.90	49+00.00	548
12	49+00.00	54+50.00	125
13	54+50.00	60+00.00	100
14	60+00.00	62+39.54	67
TOTAL			3697

COMPACTED FILL (90% MR-90)

SHEET NO.	CL STATION	CL STATION	CU. YDS.
5	11+08.03	15+50.00	101
6	15+50.00	20+77.03	565
7	20+77.03	28+50.00	532
8	28+50.00	32+00.00	173
9	32+00.00	37+75.00	51
10	37+75.00	43+65.90	282
11	43+65.90	49+00.00	192
12	49+00.00	54+50.00	40
13	54+50.00	60+00.00	88
14	60+00.00	62+39.54	28
TOTAL			2022

SWS PIPE REMOVED 0" TO 20"

SHEET NO.	CL STATION	CL STATION	LF
5	11+08.03	15+50.00	24
6	15+50.00	20+77.03	32
7	20+77.03	28+50.00	220
8	28+50.00	32+00.00	18
9	32+00.00	37+75.00	123
10	37+75.00	43+65.90	115
TOTAL			550

SWS PIPE REMOVED 21" TO 48"

SHEET NO.	CL STATION	CL STATION	LF
14	60+00.00	62+39.54	74
TOTAL			74

ASPHALT PAVEMENT REMOVAL

SHEET NO.	CL STATION	CL STATION	SQ. YDS.
5	11+08.03	15+50.00	1482
6	15+50.00	20+77.03	2497
7	20+77.03	28+50.00	1684
8	28+50.00	32+00.00	1758
9	32+00.00	37+75.00	1916
10	37+75.00	43+65.90	2272
11	43+65.90	49+00.00	1870
12	49+00.00	54+50.00	1758
13	54+50.00	60+00.00	1791
14	60+00.00	62+39.54	1447
TOTAL			18273

CONCRETE DRIVE REMOVAL

SHEET NO.	CL STATION	CL STATION	SQ. YDS.
5	11+08.03	15+50.00	19
6	15+50.00	20+77.03	128
12	49+00.00	54+50.00	139
TOTAL			288

REMOVE COMB. C & G

SHEET NO.	CL STATION	CL STATION	LF
6	15+50.00	20+77.03	16
7	20+77.03	28+50.00	24
8	28+50.00	32+00.00	23
10	37+75.00	43+65.90	11
14	60+00.00	62+39.54	56
TOTAL			130

REMOVE WIRE FENCE

SHEET NO.	CL STATION	CL STATION	LF
5	11+08.03	15+50.00	289
6	15+50.00	20+77.03	395
TOTAL			684

REMOVE SWS INLET

SHEET NO.	CL STATION	CL STATION	EA
14	60+00.00	62+39.54	1
TOTAL			1

SIDEWALK REMOVED

SHEET NO.	CL STATION	CL STATION	SQ. YDS.
5	11+08.03	15+50.00	14
TOTAL			14

TREES, SMALL REMOVED

SHEET NO.	CL STATION	CL STATION	EA
6	15+50.00	20+77.03	5
7	20+77.03	28+50.00	2
8	28+50.00	32+00.00	9
9	32+00.00	37+75.00	19
10	37+75.00	43+65.90	5
14	60+00.00	62+39.54	1
TOTAL			41

TREES, LARGE REMOVED

SHEET NO.	CL STATION	CL STATION	EA
7	20+77.03	28+50.00	1
TOTAL			1

INLET ADJUSTED

SHEET NO.	CL STATION	CL STATION	EA
14	60+00.00	62+39.54	1
TOTAL			1

SIDEWALK PVMT. 4" (AE)

SHEET NO.	CL STATION	CL STATION	SQ. FT.
5	11+08.03	15+50.00	6018
6	15+50.00	20+77.03	5433
7	20+77.03	28+50.00	4994
8	28+50.00	32+00.00	6308
9	32+00.00	37+75.00	6515
10	37+75.00	43+65.90	8542
11	43+65.90	49+00.00	8424
12	49+00.00	54+50.00	6241
13	54+50.00	60+00.00	8453
14	60+00.00	62+39.54	2884
TOTAL			57792

WHEELCHAIR RAMPS

SHEET NO.	CL STATION	CL STATION	EA
6	15+50.00	20+77.03	4
7	20+77.03	28+50.00	1
8	28+50.00	32+00.00	1
10	37+75.00	43+65.90	2
12	49+00.00	54+50.00	2
TOTAL			10

MANHOLE ADJUSTED (KDOT NON-PARTICIPATING)

SHEET NO.	CL STATION	CL STATION	EA
6	15+50.00	20+77.03	1
7	20+77.03	28+50.00	3
8	28+50.00	32+00.00	4
9	32+00.00	37+75.00	3
10	37+75.00	43+65.90	3
11	43+65.90	49+00.00	1
13	54+50.00	60+00.00	2
TOTAL			17

ADJUST FH (KDOT NON-PARTICIPATING)

SHEET NO.	CL STATION	CL STATION	EA
6	15+50.00	20+77.03	1
7	20+77.03	28+50.00	1
TOTAL			2

ADJUST WATER METER (KDOT NON-PARTICIPATING)

SHEET NO.	CL STATION	CL STATION	EA
7	20+77.03	28+50.00	1
8	28+50.00	32+00.00	1
9	32+00.00	37+75.00	4
TOTAL			6

ADJUST VALVE BOX (KDOT NON-PARTICIPATING)

SHEET NO.	CL STATION	CL STATION	EA
6	15+50.00	20+77.03	3
7	20+77.03	28+50.00	4
8	28+50.00	32+00.00	1
9	32+00.00	37+75.00	3
10	37+75.00	43+65.90	1
TOTAL			12

MANHOLE ADJUSTED

SHEET NO.	CL STATION	CL STATION	EA
5	11+08.03	15+50.00	2
6	15+50.00	20+77.03	1
7	20+77.03	28+50.00	1
TOTAL			4

ADJUST WATER METER

SHEET NO.	CL STATION	CL STATION	EA
5	11+08.03	15+50.00	1
TOTAL			1

YOUNG & ASSOCIATES, P.A.
Civil and Environmental Engineers

100 South George
Dorcy, Kansas 67037
Tel: (316) 788-2552
Fax: (316) 788-1408

City of Wichita
Sedgwick County, Kansas

S