

### BRANCH CIRCUIT PANEL SUMMARY

SVA		PANEL DESIG.	SE RATED AIC	NEMA 3R	MAINS RATING (AMPS)	MOUNTING	BRANCH CIRCUIT BREAKERS (AMPS/POLE)										SUPPLY DEVICE RATING (SW/FUSE)	CIRCUIT NUMBER	FEEDER IDENT.	
STATUS	20/1						20/2	20/3	20/4	20/5	20/6	20/7	20/8	20/9	20/10	20/11				20/12
①	A	•	•	•	225	•	ACTIVE	32	2									225/3 CB	-----	4
①	B	•	•	•	225	•	ACTIVE	20	1									225/3 CB	-----	4
①	C	•	•	•	225	•	ACTIVE	35	7									225/3 CB	-----	4

① PANELS TO BE SQUARE D POWER LINK WITH DISPLAY AND ASTRONOMICAL TIMELOCK ON EACH PANEL. PANELS TO BE PROGRAMMED BY FACTORY REPRESENTATIVE PER OWNER REQUIREMENTS. ROUTE FEEDER W/5 FROM EACH PANEL. TO MANUAL SWITCHES ON PANEL B. VERIFY ALL REQUIREMENTS WITH PANEL MANUFACTURER.

### FEEDER SCHEDULE

FEEDER IDENT.	CONDUCTORS			GROUND SIZE PER SET	ISOLATED GRD. SIZE PER SET	CONDUIT SIZE PER SET
	SETS	QUANT. PER SET	SIZE			
①	1	2	#8	#10	-----	1"
②	1	2	#10	#10	-----	1"
③	1	3	#8	#10	-----	1"
④	1	3	#3/0	#3/0	-----	3"
⑤	1	10	#12	#12	-----	1"

① MIN. 36" BELOW GRADE WITH STEEL ELLS & RISERS.  
 ② MIN. 30" BELOW GRADE.


### SPECIAL OUTLET SCHEDULE

SYMBOL	DESCRIPTION	HEIGHT
⊙	GFCI RECEPTACLE MOUNTED ON POLE. CONTRACTOR TO PROVIDE RECEPTACLE, BOX AND IN-USE COVER. PROVIDE, INSTALL AND CONNECT COMPLETE ASSEMBLY. NO EXPOSED WIRING OR CONDUIT ALLOWED. CONTRACTOR TO VERIFY ALL REQUIREMENTS WITH KGE.	6'-6" TO TOP
⊙	GFCI RECEPTACLE MOUNTED IN FLUSH GROUND MOUNTED BOX. CONTRACTOR TO PROVIDE RECEPTACLE, BOX AND IN-USE COVER. PROVIDE, INSTALL AND CONNECT COMPLETE ASSEMBLY. SEE DETAIL 2/LS 4.07.	6'-6" TO TOP
⊙	GFCI RECEPTACLE MOUNTED ON INSIDE OF TOWER MOUNTING PLATE. CONTRACTOR TO PROVIDE RECEPTACLE, BOX AND IN-USE COVER. PROVIDE, INSTALL AND CONNECT COMPLETE ASSEMBLY. EXPOSED WIRING OR CONDUIT ALLOWED ONLY WITH OWNER APPROVAL. CONTRACTOR TO VERIFY ALL REQUIREMENTS WITH OWNER PRIOR TO ROUGH-IN. SEE DETAIL 3/LS 4.07.	6'-6" TO TOP

### SYMBOL LIST

SYMBOL	DESCRIPTION	MOUNTING
⊙	FLUORESCENT FIXTURE & FIXTURE LETTER	CEILING
⊙	FLUORESCENT FIXTURE & FIXTURE LETTER	CEILING
⊙	INCAND. OR H.I.D. FIXTURE & FIXT. LETTER	SURF./RECESSED
⊙	INCAND. OR H.I.D. FIXTURE & FIXT. LETTER	WALLBRACKET
⊙	EXIT FIXT. - SHADING DENOTES FACE(S)	CEIL./WALL
⊙	GFCI DUPLEX GROUNDED RECEPTACLE	1'-3" AFF
⊙	DUPLEX GROUNDED RECEPTACLE	1'-3" AFF
⊙	EXTERIOR GFCI RECEPT. WEATHERPROOF	1'-3" AFF
⊙	SPECIAL OUTLET, SEE SCHEDULE OR AS NOTED	
⊙	SWITCHES (1-POLE, 3-WAY, 4-WAY, PILOT KEY)	4'-0" TO TOP
⊙	JUNCTION BOX	
⊙	FUSTAT	
⊙	SPECIAL DEVICE AS NOTED ON PLAN	
⊙	BRANCH CIRCUIT PANEL & PANEL DESIG.	6'-6" TO TOP
⊙	H.D. SAFETY SWITCH (AMPS/POLE/VOLTAGE)	6'-6" TO TOP
⊙	STARTER (SIZE/POLE/VOLTAGE)	6'-6" TO TOP
⊙	CONDUIT RUN 2#12 & #12 GRD. -1/2" C.	CEIL./WALL
⊙	CONDUIT RUN 2 CIRCUITS #12 & #12 GRD. -1/2" C.	EARTH/FLOOR
⊙	PARTIAL HOMERUN (MULTIPLE LOAD LOCATIONS)	
⊙	SEE NOTE #1	
⊙	CIRCUIT SUPPLIED FROM EMERGENCY SYSTEM	
⊙	FEEDER IDENTIFICATION, SEE SCHEDULE	

- ### GENERAL NOTES
- VERIFY ALL OUTLET LOCATIONS ON THE JOB PRIOR TO ROUGH-IN.
  - REFER TO RELATED ARCHITECTURAL, AND STRUCTURAL DRAWINGS FOR RELATED INFORMATION.
  - REFER TO THE SPECIFICATIONS FOR DATA NOT ON THE DRAWINGS.
  - COORDINATE OUTLET BOX LOCATIONS WITH MASONRY TO MINIMIZE CUTTING OF BRICK OR BLOCK.
  - ALL MOUNTING HEIGHTS TO BOTTOM OF ITEM UNLESS OTHERWISE NOTED.
  - CONDUIT RUN W/CONDUCTORS AS INDICATED. CONDUIT SIZE AS REQUIRED. CONDUIT RUN TO PANEL DEVICE SIZE AS INDICATED (AMP/POLE). CIRCUIT WITHOUT INDICATION IS ROUTED TO 20A, 1P, BREAKER.
  - A GROUND CONDUCTOR SIZED PER N. E. C. ARTICLE 250 IS REQUIRED IN ALL POWER, RECEPTACLE, AND LIGHTING CIRCUITS. GROUND CONDUCTORS ARE NOT SHOWN ON DRAWINGS.
  - ELECTRICAL CONTRACTOR SHALL FULLY AND CAREFULLY COORDINATE ENTIRE INSTALLATION WITH KGE FOR SERVICE ENTRANCE AND POLE EQUIPMENT LOCATIONS. KGE WILL BE SETTING NEW LIGHT POLES WITHIN THIS PROJECT AND INSTALLATION OF ALL RECEPTACLES AND WIRING SHALL BE FULLY COORDINATED BY ELECTRICAL CONTRACTOR.
  - BASE BID:  
CONTRACTOR SHALL PROVIDE ALL ELECTRICAL SERVICE ENTRANCE WORK, TO AND INCLUDING BRANCH CIRCUIT PANELS AND CONDUCTORS, CONTROL SWITCHES, FOUNTAIN CIRCUITS. BASE BID TO INCLUDE ALL BRANCH CIRCUIT CONDUITS FROM DISTRIBUTION PANELS TO POINT CONDUIT GOES ABOVE GRADE AT SPECIAL OUTLETS A, B OR C. NO BRANCH CIRCUIT CONDUCTORS, EQUIPMENT OR DEVICES FOR SPECIAL OUTLET A'S, B'S OR C'S TO BE INCLUDED IN BASE BID.
  - ALTERNATE BIDS:  
(REFER TO BID FORM FOR DESCRIPTION OF ALL ALTERNATES)
  - PROVIDE ALL BRANCH CIRCUIT, CONDUITS, CONDUCTORS, DEVICES AND EQUIPMENT FOR SPECIAL OUTLET A'S AS INDICATED ON THE DRAWINGS. ALTERNATE BID TO BE AN AMOUNT TO ADD TO BASE BID FOR A COMPLETE PROJECT.
  - PROVIDE ALL BRANCH CIRCUIT CONDUCTORS, DEVICES AND EQUIPMENT FOR SPECIAL OUTLET B'S AND C'S AS INDICATED ON THE DRAWINGS. ALTERNATE BID TO BE AN AMOUNT TO ADD TO BASE BID FOR A COMPLETE PROJECT.



Electrical Engineering and Design  
 349 S. Hydraulic  
 Wichita, Ks. 67211-1908  
 (316) 264-3061  
 FAX: (316) 264-3542

**MID-KANSAS ENGINEERING CONSULTANTS, INC.**  
 411 N. WEBB ROAD  
 WICHITA, KS. 67206  
 316-684-9600

**STREETSCAPES**  
 PROJECT NAME

**SCHEDULES AND RISER**  
 SHEET TITLE

SVA	SVA	SVA
DESIGN BY:	DRAWN BY:	CHECKED BY:
MAY 1998	92010	LS 9.02
DATE	JOB NO.	SHEET OF

REV. MAY, 1999