




1. REMOVE DOOR(S), DOOR FRAME, THRESHOLD IF PRESENT FROM EXISTING OPENING.
2. REMOVE THRU-WALL LOUVERS.
3. REMOVE PORTION OF EXISTING GYP. BD. PARTITION AS REQUIRED FOR ACCESSING NEW WORK.
4. REMOVE EXTERIOR MASONRY WALL DOWN TO LOCATION SHOWN ON ELEVATIONS. SALVAGE & CLEAN BRICK FOR REUSE.
5. REMOVE EXISTING HANDRAIL.
6. REROUTE EXISTING MTL FLUE, FROM EXT. TO INTERIOR.
7. REMOVE TERRACE WALL AND BRICK VENEER FROM FACE OF FOUNDATION. SALVAGE BRICK, PRECAST CAPS, AND CAST ORNAMENTAL GRILLES FOR RECONSTRUCTION.
8. REMOVE WINDOW TO OWNER STORAGE.
9. REMOVE MASONRY INFILL FROM ORIGINAL OPENING.
10. REMOVE EXISTING STEEL UNTEL, SHORE AS REQUIRED.
11. STAIR WALLS HAVE BEEN PARTIALLY REMOVED DOWN TO TREADS & LANDING. TO COMPLETE THE REMOVAL & SALVAGE BRICK FOR RECONSTRUCTION.
12. REMOVE EXISTING LAYERS OF CONC. TOPPING FROM TERRACE, DOWN TO STRUCTURAL SLAB.
13. REMOVE EXISTING LAYERS OF CONC. TOPPING FROM TREADS & LANDING, DOWN TO STRUCTURAL SLAB.
14. REMOVE EXISTING MASONRY PLASTER, PROVIDE TEMPORARY SHORING AS REQUIRED.
15. REMOVE EXISTING WINDOW.
16. REMOVE MASONRY BELOW WINDOW OPENING, DOWN TO FLOOR.
17. REMOVE & SALVAGE CAST ORNAMENTAL GRILLES FOR REUSE. REFER GENERAL NOTE A.
18. REMOVE EXISTING CONCRETE SIDEWALK.
19. REMOVE FACE BRICK // PLASTER VENEER, & REPLACE // SALVAGED & CLEANED BRICK. REMOVE & REPLACE IN SMALL ENOUGH SECTIONS TO MAINTAIN OVERALL STRUCTURAL INTEGRITY.
20. REMOVE FLOOR ABOVE & FLOOR FRAMING. REMOVE ALL NON-ORIGINAL BRICK @ BEARING POCKETS & ELSEWHERE.
21. REMOVE ALL G.I. MTL. FLASHING FROM WALL, TYPICAL.
22. REMOVE ALL INTERIOR GYP. BD. FINISHES & ASSOCIATED FRAMING.
23. REMOVE LOUVER & ASSOCIATED INFILL. PREPARE OPENING FOR NEW WINDOW.
24. REMOVE ALL EXISTING COPING FROM VESTIBULE.
25. REOPEN PREVIOUS OPENING FOR NEW WINDOW.
26. REMOVE REMAINING PLASTER FROM WALLS @ THIS AREA.
27. REMOVE UNSOUND PLASTER FROM WALLS @ THIS AREA.

FIRST FLOOR REMOVAL PLAN
SCALE: 1" = 8'-0"

