

SYMBOLS

008 DOOR DESIGNATION

M REFURBISH EXISTING WINDOW

M NEW PROVIDE NEW WINDOW

DOOR, FRAME + HARDWARE SCHEDULE

DOOR TAG	DOOR PR.	* W	* H	MAT.	GL.	TYPE	FIRE LABEL	FRAME MAT.	GL.	TYPE	DETAILS THRESHOLD	JAMBS	HEAD	HDW SET	REMARKS
001	PR	3-0	7-0	WD	T	G1	–	HM	–	9	1&3/A6.2	2&4/A6.2	4/A6.2 SIM.	3	–
002	–	2-10	7-0	WD	O/T	G1	–	HM	–	4	5&7/A6.2	6&8/A6.2	7/A6.2 SIM.	6	–
003	–	3-4	7-0	WD	O/T	G1	–	HM	–	6	5&7/A6.2	6&8/A6.2	7/A6.2 SIM.	6	–
004	PR	3-5	7-0	WD	T	G1	–	HM	–	13	1&3/A6.2	2&4/A6.2	3/A6.2 SIM.	1	1
005	–	3-2	7-0	WD	T	G1	–	HM	–	5	1&3/A6.2	2&4/A6.2	3/A6.2 SIM.	5	–
006	PR	3-2	7-0	WD	T	G1	–	HM	SG	19	13/A6.2	14/A6.2	15&16/A6.2	1	1
007	PR	3-0	7-0	WD	T	G1	–	HM	T	15	1/A6.1	7,8&9/A6.1	9/A6.1 SIM.	7	1
008	–	3-2	7-0	WD	T	G1	–	HM	–	5	1&3/A6.2	2&4/A6.2	3/A6.2 SIM.	5	–
009	PR	2-11	7-0	HM	T	G1	–	HM	–	10	1&3/A6.2	2&4/A6.2	3/A6.2 SIM.	10	1
010	–	3-8	7-0	HM	O/T	G1	–	HM	SG	18	5&7/A6.2	6&8/A6.2	11&12/A6.2	6	2
011	–	3-8	7-0	WD	O/T	G1	–	HM	SG	18	5&7/A6.2	6&8/A6.2	11&12/A6.2	6	2
012	–	3-0	7-0	WD	O/T	G1	–	HM	SG	16	5&7/A6.2	6&8/A6.2	11&12/A6.2	6	2
013	PR	2-8	7-0	WD	T	G1	–	HM	–	3	1&3/A6.2	2&4/A6.2	4/A6.2 SIM.	3	–
014	–	3-6	7-0	WD	O/T	G1	–	HM	SG	17	5&7/A6.2	6&8/A6.2	11&12/A6.2	6	2
015	PR	–	7-0	HM	–	F	–	HM	–	8	10&12/A6.1	11&13/A6.1	13/A6.1 SIM.	4	–
016	PR	–	7-0	HM	–	F	–	HM	–	12	1&3/A6.2	2&4/A6.2	4/A6.2 SIM.	2	–
017	PR	3-0	7-0	WD	O/T	G1	–	HM	–	11	5&7/A6.2	6&8/A6.2	8/A6.2 SIM.	6	1
018	–	2-8	6-6	HM	–	F	–	HM	–	1	3/A6.2	4/A6.2	4/A6.2 SIM.	8	–
–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–

* VERIFY ACTUAL FRAME OPENING DIMENSIONS W/ H.M. FRAME SHOP DRAWINGS.
WOOD DOORS 2" THICK
H.M. DOORS 1 3/4" THICK

DOOR & FRAME MATERIAL
HM HOLLOW METAL
WD WOOD

GLAZING MATERIAL
IN INSULATED
O OBSCURE
SG SAFETY GLASS
T TEMPERED

REMARKS
1. REMOVABLE CENTER MULLION
2. FIXED, WOOD DIVIDED LITE TRANSOM
3. –
4. –

GENERAL NOTES

A. OWNER RESPONSIBLE FOR MOVING EXHIBITRY AND STORED ITEMS AWAY FROM ALL AREAS REQUIRING NEW WORK. @ ALL FLOORS.

B. PREPARE, REFINISH & REPUTTY ALL EXISTING STEEL WINDOWS, TYPICAL. REFER WINDOW SPEC. TYPICAL, ALL FLOORS.

C. MASONRY MATERIALS SALVAGED FROM REMOVED FRONT TERRACE STAIR WALLS ARE STORED BELOW THE TERRACE.

PLAN NOTES

1. INFILL REMAINING OPENING WITH LIKE MASONRY MATERIALS.
2. PROVIDE NEW LIGHTED, CEILNG MOUNTED, DIRECTIONAL EXIT SIGN TO NORTH EXIT. PROVIDE BATTERY BACKUP.
3. REPLACE PORTION OF EXISTING GYP. BD. PARTITION AS REMOVED FOR ACCESSING NEW WORK.
4. EXISTING RETAINING WALL.
5. REPLACE EXISTING SUSPENDED ACOUSTICAL CEILING SYSTEM AS REQUIRED.
6. RELOCATE EXISTING METAL FLUE.
7. EXISTING FURRED WALLS TO REMAIN.
8. NEW INACTIVE DOOR, STOPPED BOTH SIDES. NO LOCKSET, TYPICAL.
9. NEW STEEL LINTEL & RECONSTRUCT REMOVED MASONRY VENEER & TERRACE WALLS.
10. PATCH & PAINT GYP. BD. & INTERIOR FINISHES AROUND NEW STEEL WINDOW.
11. GYP. BD. ON 7/8" MTL. FURRING CHANNELS.

NORTH

0 8' 16' 24' 32'

GROUND FLOOR RENOVATION PLAN

SCALE: 1" = 8'-0"

FEWA REC. NO.	STATE	PROJECT NO.	YEAR	NO. SHEETS
7	KANSAS	TE-1007(502) 087 TE-0075-02	2004	A2-0 15

SCHAEFER JOHNSON COX FREY & ASSOCIATES PA
ARCHITECTURE ENGINEERING PLANNING & INTERIOR DESIGN
257 N. BROADWAY
WICHITA, KANSAS 67202-2317
(316) 684-0171
FAX (316) 684-8836

KANSAS AVIATION MUSEUM

3350 S. GEORGE WASHINGTON BOULEVARD WICHITA, KANSAS

REVISION DATE
PROJECT NO. 2632.10
DATE APRIL 2004
A2-0

M:\2632.10\A2-0.DWG
1/8" = 1'-0"

©2000, SCHAEFER JOHNSON COX FREY & ASSOCIATES PA